

## **Washington County Landfill**

### **Q & A's**

**June 17, 2025**

1. Testing? – All testing will be done by American Environmental Consulting.
2. Surveying? – American Environmental Consulting will arrange for and provide all the surveying needed for the project.
3. Compaction? -- Specs in the plan. Can use sheepsfoot compaction.
4. Construction water? – The County will arrange for access to buy water from the town of Akron.
5. Fill outside of the line limit on the drawings? -- Not necessary to fill outside of the lined area of the cell.
6. Ground water issues? – No issues with depth to ground water.
7. Stormwater control? -- Yes, the contractor must plan and provide for storm water control with a berm.
8. Squaring up the east edge? -- It involves mostly filling to get grade even and correct depth.
9. Coordinate with the Synthetic Liner Contractor? – Yes, the earthwork contractor must coordinate with the Liner contractor. The Liner work will generally take 5-6 days, maybe up to 14 days depending on the weather. Then the earthwork contractor must come in to finish the scope of work.
10. How far does the liner come up the sides of the cell? -- The liner comes all the way on 3 sides, and is anchored into the first cell on the east side of the new cell.
11. How much cut on the west side of the cell? -- Quite a bit of cut, used for fill.
12. Is this a prevailing wage project? -- No
13. Is the project tax-exempt? -- Yes
14. Is a bid bond required? -- Yes